

1.0 GENERAL

1.1 Scope

1.1.1 The work shall consist of the removal and disposal of Asphalt or Plain Concrete Pavements.

1.2 Related Sections

1.2.1 Section 02010 – Sawcutting

1.2.2 Section 02050 – Concrete Removal

2.0 PRODUCTS

None in this section

3.0 EXECUTION

3.1 Construction

3.1.1 The removal and disposal of asphalt pavement and plain concrete shall be completed in a safe manner, meeting all Occupational Health and Safety requirements.

3.1.2 Complete sawcutting in accordance with Section 2010 for Sawcutting.

3.1.3 Proper barricades and traffic accommodation shall be erected and maintained by the Contractor for protection as set out in the City of Regina Temporary Traffic Control Manual.

3.1.4 Removal of asphalt pavement and plain concrete pavement when required for the removal and replacement of sidewalks curb and gutters shall be considered a subsidiary obligation under removal of curb or curb and gutter. Any asphalt or concrete pavement removed outside the designated limits without prior approval by the Engineer shall be replaced to the original or better condition, at no additional cost.

3.1.5 Asphalt or concrete pavements shall be removed from the site. Any temporary stockpiles at the site shall be neatly stockpiled until removed.

3.1.6 If asphalt and concrete pavement removed is disposed of at the City of Regina Landfill, the maximum size of the removed concrete shall not exceed 600mm in any direction. The City of Regina Landfill reserves the right to reject any load containing material(s) not meeting its specifications. Refer to City of Regina Landfill for further information regarding asphalt and concrete waste and disposal.